

**LINCOLN COUNTY HIGHWAY DEPARTMENT**

Post Office Box 97  
Ivanhoe, Minnesota 56142

Joseph M. Wilson, P.E.  
E-Mail: jwilson@co.lincoln.mn.us  
Phone: 507-694-1464  
Fax: 507-694-1101

**ADDENDUM**


Date: July 9, 2020  
To: All Planholders of Record  
Subject: Contract No. 02-2020  
Addendum No. 2  
Date of Letting: July 14, 2020

**A) Plan Addendum Items**

1. **Schedule of Prices Dated 7/7/2020** is hereby removed and replaced with the attached updated Schedule of Prices Dated 7/9/2020 and "Addendum 2" written in the upper left corner. Changes were made to quantities of "Place Concrete Pavement" and "5 Concrete Walk" to match Addendum 1.

Bidders shall acknowledge the receipt of this addendum according to the provisions of Mn/DOT 1210.

Sincerely,



Joseph M. Wilson, P.E.  
Lincoln County Engineer

**Attachments:** Amended Schedule of Prices (2 Pages)

Addendum 2

7/9/2020

Contract No.: 02-2020

LCHD  
Schedule Of Prices

Project Number: 02-2020

Project Title or Road Number: County Parking Lot Improvements

Work Type: Concrete Paving &amp; Sidewalk

BIDDER MUST FILL IN UNIT PRICES IN NUMERALS; MAKE EXTENSION FOR EACH ITEM AND TOTAL. FOR COMPLETE INFORMATION CONCERNING THESE ITEMS, SEE PLANS AND SPECIFICATIONS, INCLUDING SPECIAL PROVISIONS.

Item No.	Description	Units	Quantity	Unit Price	Total Price
2021.501	MOBILIZATION	LUMP SUM	1.00		
2101.501	CLEARING & GRUBBING	LUMP SUM	1.00		
2102.503	PAVEMENT MARKING REMOVAL	LIN FT	132.00		
2102.518	PAVEMENT MARKING REMOVAL	SQ FT	20.00		
2104.502	REMOVE CATCH BASIN & CASTING	EACH	1.00		
2104.502	SALVAGE HANDICAP SIGN	EACH	3.00		
2104.503	REMOVE CURB AND GUTTER	LIN FT	300.00		
2104.518	REMOVE SIDEWALK	SQ FT	715.00		
2104.518	REMOVE CONCRETE PAVEMENT	SQ FT	980.00		
2104.518	REMOVE VALLEY GUTTER	SQ FT	75.00		
2104.518	REMOVE BITUMINOUS PAVEMENT	SQ FT	580.00		
2105.507	COMMON EXCAVATION (P)	CU YD	880.00		
2211.509	AGGREGATE BASE CLASS 5	TON	720.00		
2211.607	3/4" CRUSHED ROCK	CU YD	114.00		
2301.504	PLACE CONCRETE PAVEMENT	SQ YD	772.00		
2357.506	BITUMINOUS MATERIAL FOR TACK COAT	GALLON	10.00		
2360.504	TYPE SP 12.5 WEARING COURSE MIXTURE (2,B) 4.0" THICK	SQ YD	65.00		
2503.503	8" PIPE SEWER DESIGN, PERFORATED HDPE	LIN FT	465.00		
2503.503	16" PIPE SEWER DESIGN, HDPE	LIN FT	4.00		
2506.502	CASTING ASSEMBLY - R2557	EACH	1.00		

BIDDER MUST FILL IN UNIT PRICES IN NUMERALS; MAKE EXTENSION FOR EACH ITEM AND TOTAL. FOR COMPLETE INFORMATION CONCERNING THESE ITEMS, SEE PLANS AND SPECIFICATIONS, INCLUDING SPECIAL PROVISIONS.					
Item No.	Description	Units	Quantity	Unit Price	Total Price
2506.502	CASTING ASSEMBLY - R3067	EACH	1.00		
2506.502	CASTING ASSEMBLY - R3076	EACH	1.00		
2506.503	CONSTRUCT DRAINAGE STRUCTURE 4' DIA STORM MANHOLE	LIN FT	4.17		
2506.503	CONSTRUCT DRAINAGE STRUCTURE 2' X 3' CATCH BASIN	LIN FT	7.58		
2511.504	GEOTEXTILE FILTER TYPE 3	SQ YD	227.00		
2521.518	5" CONCRETE WALK	SQ FT	944.00		
2531.503	CONCRETE CURB AND GUTTER DESIGN B612	LIN FT	335.00		
2531.503	CONCRETE CURB AND GUTTER DESIGN B618	LIN FT	136.00		
2531.603	CONCRETE VALLEY GUTTER	LIN FT	17.00		
2531.618	TRUNCATED DOMES	SQ FT	28.00		
2563.601	TRAFFIC CONTROL	LUMP SUM	1.00		
2573.502	STORM DRAIN INLET PROTECTION	EACH	3.00		
2574.507	COMMON TOPSOIL BORROW	CU YD	121.00		
2574.508	FERTILIZER TYPE 3	POUND	45.00		
2575.505	SEEDING	ACRE	0.14		
2575.508	SEED MIXTURE 25-131	POUND	20.00		
2575.508	HYDRAULIC MULCH MATRIX	POUND	224.00		
2582.518	PAVEMENT MESSAGE (HANDICAP) EPOXY	SQ FT	30.00		
2582.603	LINEAR MARKING 4" WIDE EPOXY WHITE	LIN FT	508.00		
Total					

**Bidder Name:** \_\_\_\_\_

**Bidder Address:** \_\_\_\_\_

**Bidder Phone:** \_\_\_\_\_

**Bidder Signature:** \_\_\_\_\_

**Date:** \_\_\_\_\_